NO CEILING.
I.B.R. SHEETING
101 CONC. FLOOR.
101 ϕ STEEL PIPES

ELEVATION (OPEN TO FRONT.)

228 X 076 TIMBER RAFTERS
076 X 076 BRANDERING.
ROOF REMOVED
STEEL COL. REMOVED
2,74 Floor to o/s roof
2,59 Floor to o/s roof
304 x 609
304 x 609

SECTION E-E.

358499

EX. OPEN AREA.

EX. TIMBER STORAGE TO REMAIN.

EX. TIMBER STORAGE TO REMAIN.

EXISTING BOUNDARY WALL TO REMAIN.

TIMBER STORAGE. (No 1)
(TO BE DEMOLISHED)

EL. DOORS REMOVED

ROOF OVER FLOOR REMOVED

5,000

PLAN OF COVERED BUILDING.

25,000

2,3m

'B'

'B'

EX TIMBER STORAGE TO REMAIN.

NEW OPEN COVERED AREA.

101 ϕ STEEL SUPPORTS.

(No. 2)

17,500

ELEVATION TO 'CEMENT STORAGE' STOREROOM.

228 X 076 TIMBER RAFTERS
076 X 076 BRANDERING
NO CEILING.
I.B.R. SHEETING.
101 CONC. FLOOR SLAB.

2,74 Floor to o/s roof.
2,59 Floor to o/s roof.
304 x 609
304 x 609

SECTION A-A

NOTES:

NO PROPOSED DRAINAGE.
AREA 299,1 m²

To Existing MH 13-7-79
SEWER AVAILABLE

EX TIMBER STORAGE TO REMAIN

5,300

15,410

Trees to remain.

EX SHOP

NEW CEMENT STORAGE.

NEW CEMENT STORAGE.

4,780

5,000

220

7,700

220

7,300

220

220

PLAN (No 3)

'D'

'C'

'D'

EX. COVERED STORE TO BE ENCLOSED. (No. 4.)

EX. S/ROOM.

EX. OFFICE TO REM.

EX.

EX. OFFICE

EX. KEY CUTTING.

EX. DOOR KNOBS.

EX. SHOP TO REMAIN.

EX. SHOP TO REMAIN.

EX. SEEDS.

PLAN OF SHOP & YARD BUILDINGS (1:100)

220 X 076 TIMBER RAFTERS.
076 X 076 BRANDERING
NO CEILING.
101 CONC. FLOOR.

(No. 2.)

ELEVATION TO NEW COVERED AREA OPEN TO FRONT.

EX.

PROPOSED NEW.

228 X 076 TIMBER RAFTERS.

228 X 076 TIMBER BEAM.

3,000 Floor to o/s roof.

2,700 Floor to o/s roof.

Ex. footings.

304 X 609.

SECTION 'B-B'

EXISTING.

NEW COVERED AREA No 1. TO BE REMOVED.

BAY 3

BAY 1

BAY 2

NEW COVERED AREA (No. 2)

5,500

544

NEW CEMENT STORE (No. 3)

EXISTING

Ex. STORE ENCLOSED (No. 4)

Trelodic ACCESS

EX SHOP TO REMAIN.

5,300 WIDE

EX. STORE ENCLOSED.

542

540

JAN SMUTS AVENUE.

SITE PLAN (SCALE 1:500)

4/9/79.

228 X 076 TIMBER RAFTERS.
076 X 076 BRANDERING
NO CEILING.
1.B.R. SHEETING
101 CONC. FLOOR SLAB.

EXISTING TO REMAIN

EX STORE (FRONT ENCLOSURE.)

ELEVATION.

(EXISTING STORE ENCLOSED.) (No. 4)

3,500

3,000

Ex. footings

304 x 609

SECTION 'D-D'

NOTE:
ALL DRAINS ENCASED IN CONC.
WHERE NEW FOUNDATIONS OCCUR. ALL LOADING & OFF LOADING WILL TAKE PLACE ON SITE.

18/9/79

PROPOSED

EXISTING.

228 X 076 timber rafters
076 X 076 BRANDERING.
NO CEILING.
101 conc. floor slab.

2,74 Floor to o/s roof.

2,59 Floor to o/s roof.

SECTION 'C-C'

ELEVATION TO ENCLOSURE OF EX STORE. (No. 5)

OWNER: Craig Hardware

DATE: 11-6-79.

PROPOSED ADDITIONS. CRAIG HARDWARE. STANDS 542 & ~~540~~ CRAIGHALL PARK.

DRAWN BY JOHN HYND
48-6543